




1:70



1:70



1:70



1:70



1:70



1:70

GENERAL

- All dimensions are shown in millimeter and feet unless otherwise stated.
- Drawings are not to be scaled. only figured dimensions to be used.
- The contractor must check all dimensions on site before commencement of any work.

- All slabs at ground level to be poured over 500 ga polythene sheeting on 50mm thick murrum blinding hardcore.
- All soil under slabs and around external foundation to be poisoned for termite control.

-All soils on cut embankments to be stabilized. the slope not to exceed the natural angle of repose.

- All black cotton soils to be removed from below all buildings and paved surfaces.
- For all R.C. work, refer to structural engineer's details.
- Depth of foundations to be determined on site.
- All walls less than 150mm thick to be reinforced with hoop irons at every course.
- All adjacent R.C work and masonry walls to be tied with strip irons at every course.

- All plumbing and drainage to comply with authority specifications.
- SVP denotes soil vent pipe to be provided at the h of the drainage system.
- Drains passing beneath the building and driveway to be encased in 150mm concrete surround.
- All suspect chambers covers and framing shall cast iron with BS5525
- All underground foul and waste drain pipes shall be uPVC to comply.
- The storm drain pipes to comply with BS 556.
- Minimum slope in the drain pipes to be 1%.
- All mechanical work must be coordinated with electrical work. Conflicts must be clarified before work begins.
- P.V denotes permanent ventilations above windows and doors.

[illegible]

CLIENT: NG CDF KITUI CENTRAL