REPUBLIC OF KENYA

MINISTRY OF PUBLIC WORKS, ROADS AND TRANSPORT

PROPOSED RENOVATION

OF

4NO. CLASSROOMS BLOCK

AT

KOSEGE PRIMARY SCHOOL

SUNA WEST SUB – COUNTY

BILL OF QUANTITIES

SUB COUNTY WORKS OFFICER
MINISTRY OF P.W.R.T & E
P.O.BOX 265
MIGORI

KOSEGE PRIMARY SCHOOL
P.O BOX 278- 40400
SUNA - MIGORI

FY 2026-2027

BILL NO. 1: SUB STRUCTURE WORKS

BILL NO. 1: CONT'D

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	.				
	Plinth area finishes				
A	12mm thick cement sand [1:3] wood float render to plinth area.	Sm	42		
B	Prepared and apply three coats of bituminous black paint to rendered plinth area.	Sm	42		
	Carried to collection				

BILL NO.2: WINDOWS

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Supply and fix the following ex-shaped purpose made welded mild steel casement windows comprising of standard Z-section framing including all couping mullions and/or transoms metal gauze permanent vents complete with approved fasteners and stays as described in:				
A	1200 × 1000 mm High	No	20		
	Window Cill				
B	100 × 150 mm Clay tile window cill bended in cement and sand [1:3] mortar	Lm	40		
	Glazing				
	4 mm thick clear sheet glass in metal putty in:				
C	Panes exceeding.0. 50sq.metre but not exceeding 1.0sq.metre	Sm	18		
	Prepare and apply one undercoat and two finishing gloss oil paint to:				
D	General surface of metal [windows] internally	Sm	29		
E	General surface of metal [windows] externally	Sm	29		
	Total for Bill No. 2 windows carried forward to summary page				

BILL NO .3: DOORS

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Steel Doors				
A	1200×2400 mm high single leaved doors to details	No	4		
	4 mm thick clear sheet glass in metal putty in:				
B	Panes exceeding. 50sq.metre but not exceeding 1.0sq.metre	Sm	2.7		
	Prepare and apply three coats of super gloss oil paint on :				
C	General surfaces of metal doors internally and externally	Sm	5		
	Total for Bill No 3. Doors carried to summary page				

BILL NO .4:FINISHES

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	FLOORS FINISHES				
	Cement and [1:3] screed as described				
A	40 mm thick coloured screed in 3mm backing steel troweled smooth	Sm	198		
	WALL FINISHES				
B	12 mm thick cement sand plaster (1:4) finished smooth with steel trowel as described to gables	Sm	40		
	12mm thick cement sand render (1:4) finished smooth with steel trowel as described to walls internally and externally	Sm	168		
	Carried to collection				

BILL NO.4: CONT'D

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Painting and decoration				
	Prepare and apply one undercoat and two finishing coats of emulsion paint on:				
A	Rendered surfaces	Sm	362		
	INTERNAL WALL FINISHES				
	15 mm thick cement sand plaster (1:4) finished smooth with steel trowel as described:				
B	Walls	Sm	119		
	Paintings and decoration				
	Prepare and apply one undercoat and two finishing coats of gloss oil paint on:				
C	Plastered surfaces	Sm	198		
	Prepare and apply one undercoat and two finishing coats of bitumistic paint to black board on:				
D	Plastered chalkboard surfaces	Sm	12		
	Total for Bill No. 4.Finishes carried forward to summary page				

BILL NO.4: CONT'D

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	COLLECTION				
A	Total brought forward from page 6				
B	Total brought forward from page 7				
	Total for Bill No. 4.Finishes carried forward to summary page				

BILL NO. 5: ROOFING

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Roofing and rain water Disposal (Provisional).				
	Construction.				
	All timber to be sawn Blue gum of G.S grade Seasoned to an equilibrium moisture content of Between 9% and15% and to the requirement And treated with approved wood preservative.				
A	200x25mm thick fascia and verge boards.	Lm	101		
	Roof covering.				
B	Gauge 30 Company pre-painted iron sheets	Sm	228		
C	Half round ridge cap to match roof Covering.	Lm	25		
	Painting.				
	Prime only back of wood before fixing.				
D	General surface of wood 150-200mm girth.	Lm	25		
	Knot prime stop and prepared and apply one Undercoat and two finishing coats of gloss oil Paint to:				
E	General surfaces of wood 150-200mm girth.	Lm	25		
	Total for Bill No. 4; Roofing Works carried to summary page				

SUB TOTAL PAGE

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
A	Sub structure works				
B	Windows				
C	Doors				
D	Finishes				
E	Roofing				
	TOTAL CARRIED TO GRAND SUMMARY				

PROPOSED RENOVATION OF 4NO. CLASSROOMS
AT KOSEGE PRI. SCHOOL. **BILL OF QUANTITIES**

GENERAL GRAND SUMMARY PAGE

ITEM	DESCRIPTION	PAGE	CONTRACTOR 'S SUM		OFFICIAL USE	
			KSHS.	CTS	KSHS	CTS
1.	TOTAL FOR MEASURED WORKS					
.2	ADMIN ALLOWANCE		50,000			
	SIGN POST AND BRANDING		15,000			
	SUB TOTAL 1					
	VAT INCLUSIVE					
	GRAND TOTAL					

AMOUNT IN WORDS (KSHS) .

CONTRACTOR……..

SIGNATURE……STAMP……...DATE…….…….

G.S.