EXCAVATION OF SECURITY TRENCH AROUND PANGANI POLICE STATION

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	(ALL PROVISIONAL)				
	BUSH CLEARING				
	Site Preparation				
A	Clear site of bushes, shrubs and small trees not exceeding 300mm girth including grubbing up roots, burn or cart away arisings.	2400	SM		
	MECHANICAL EXCAVATION				
B	Mass excavation depth not exceeding 2.0 metres and hip all the excavated soil on the inner side of the property line to for a security moat..	1920	CM		
	MOBILIZATION/DEMOBILIZATION				
C	Allow for transportation of earth moving equipments to and from site.		ITEM		
	TOTAL				
	0.03% PPRA LEVY				
D	Allow for Pmc Allowances of kenya Shillings Seventy Four Thousand. (74,000) Only		ITEM		74,000.00
	TOTAL CARRIED TO FORM OF TENDER				